

Daily Thermetrics Field Services

Tubeskin Installation Task List

1	Demo Assemblies and/or Drill New Entries
2	Weld New Couplings on Heater Entries (as needed)
3	Prep Pipe Surfaces
4	Inspection of Prepped Pipe Surfaces (PT and PMI)
5	Bend/Route Assemblies
6	Weld Assemblies (Pad/Clip/Shield)
7	Monitor Temperatures during Welding
8	Inspection of Welded Assemblies (PT and PMI)
9	Assembly of External Components
10	Final Certification of Installation (Buy-Off)